



Schedule for Openings

NOTE: ALL SILL AND LEVEL LEVELS ARE TO BE TAKEN FROM FINISHED FLOOR OF RESPECTIVE ROOM.

Door	Type	Width	Sill Lvl	Level Lvl/Swing	Q.L.	Q.C.	PL	TI	Comments
D1	750	00	2100	One Way 12	16	2	30	Single leaf fire board door (leaves)	
D2	750	00	2100	One Way 0	8	0	0	Single leaf fire board door with ventilation grill (leaves)	
D3	800	00	2100	One Way 2	8	0	0	Single leaf fire board door with ventilation grill (leaves)	
D4	1000	00	2100	One Way 2	8	0	10	Single leaf fire board door with ventilation grill (leaves)	
D5	1000	00	2100	One Way 0	1	0	0	Single leaf fire board door with ventilation grill (leaves)	
D6	1000	00	2100	One Way 0	1	0	0	Single leaf fire board door with ventilation grill (leaves)	
D7	1000	00	2100	One Way 0	1	0	0	Single leaf fire board door with ventilation grill (leaves)	
D8	600	00	2100	One Way 0	4	4	4	Single leaf fire board door (leaves)	
D9	1500	00	2100	One Way 0	1	0	1	Single leaf fire board door with (Crew Control Area)	
D10	1150	00	2100	One Way 2	4	2	8	As per IIT specification.	

Rolling Shutters:

Type	Width	Sill Lvl	Level Lvl/Swing	Q.L.	Q.C.	PL	TI	Comments
RS1	3000	00	3300	-	7	0	7	MS Galvanized shutter of minimum 16 gauge with synthetic paint (metal/PU).
RS2	4000	00	3000	-	0	2	0	MS Galvanized shutter of minimum 16 gauge with synthetic paint (metal/Concourse entry).
RS3	3000	00	3500	-	0	1	0	MS Galvanized shutter of minimum 16 gauge with synthetic paint (metal/Concourse entry).
RS4	4000	00	3000	-	2	0	2	MS Galvanized shutter of minimum 16 gauge with synthetic paint (metal/Entry Structure).

Windows/Ventilators:

Type	Width	Sill Lvl	Level Lvl/Swing	Q.L.	Q.C.	PL	TI	Comments
W1	800	RL 3750	2100	Open Way 0	1	0	1	Aluminum window with fixed glazing (General)
W2	2100	2400	600	0	3	0	0	Aluminum window with fixed glazing (S&T room/G)
W3	2850	1050	1050	0	1	0	1	Aluminum window with fixed glazing (S&T room/G)
W4	2850	1050	1050	0	1	0	1	Aluminum window with fixed glazing (S&T room/G)
W5	2850	1050	1050	0	1	0	1	Aluminum window with fixed glazing (S&T room/G)
W6	2100	2000	1000	0	0	0	0	Aluminum window with fixed glazing (S&T room/G)
W7	4850	1350	750	2100	0	5	0	Aluminum window with fixed glazing (S&T room/G)
W8	4850	1350	750	2100	0	5	0	Aluminum window with fixed glazing (S&T room/G)
W9	3200	3000	300	3300	0	6	0	Aluminum window with fixed glazing (S&T room/G)
W10	4850	1350	750	2100	0	5	0	Aluminum window with fixed glazing (S&T room/G)
W11	3200	3000	300	3300	0	6	0	Aluminum window with fixed glazing (S&T room/G)
W12	4850	1350	750	2100	0	5	0	Aluminum window with fixed glazing (S&T room/G)

ROOM SCHEDULE

Room No.	Type of Room	Req. Area (sq.m)	Site of Room Area (sq.m)
U21	ESCALATOR PANEL ROOM	1.5X3	1.6X3.5
-	ANCILLARY BUILDING	-	40.0X6.1
-	-	-	7X12.4
-	-	-	86.8

GOOD FOR CONSTRUCTION

Certified that this document has been designed and checked in accordance with DDC Quality Assurance Plan.

DELHI METRO RAIL CORPORATION LTD.
Phase II: Central Secretariat Station to Badarpur Corridor
BADARPUR STATION
GROUND LEVEL PLAN
237342/BAD/DA/AR/1003

Y.D Sharma
On Approval
Authorised Signatory for DDC Madhya Pradesh

28.08.09

ARCHITECTURAL